



THE PARK at CHAPEL HILL
 CHAPEL HILL, NC
 CONCEPT SITE PLAN
 26 MARCH 2018




MCADAMS



WOODFIELD
 DEVELOPMENT

BOOKER CREEK WETLANDS



THE PARK at CHAPEL HILL
CHAPEL HILL, NC
CONCEPT SITE PLAN
26 MARCH 2018



MCADAMS




WOODFIELD
DEVELOPMENT


THE PARK AT CHAPEL HILL APARTMENTS

CHAPEL HILL, NC
3-01-18 REVISED
3-16-18 PHASE 2 ADDED

ZONING: WR-7
EPHESUS FORDHAM FORM DISTRICT
FRONTAGE TYPE: A-1
SETBACKS:
FRONT 0' MIN. UP TO 10' MAX.
SIDE (n/a)
REAR (n/a)
BUILD TO ZONE (BTZ): 80% OF BUILDING FACADE
OUTDOOR AMENITY SPACE RATIO: 0.06
req'd: 139,367 SF X .06= 8362 SF
4159 SF ON SITE, 4167 SF ACROSS ELLOITT RD
RECREATION SPACE RATIO: 0.12 Gross- TBD
BUILDING PASS THROUGH:
12' WIDE 1 STORY HIGH
330' MAX SPACING
BLOCK PARAMETERS:
MAX BLOCK LENGTH 450'
MAX. BLOCK PERIMETER 1800'
(ACTUAL 1483')
PEDESTRIAN ACCESS : 100'
TREE PLANTING ZONE : 8'
SIDEWALK: 10'
STRUCTURED PARKING: 30' MIN FROM BUILDING FACADE



PHASE 2
102 UNITS
186 PARKING SPACES +/-



KEY POINTS

- **ELLIOTT EXTENSION RIGHT OF WAY LAND CONTRIBUTION: \$3,000,000**
 - PLUS A \$50,000 CONTRIBUTION TO COVER MINOR ROAD CHANGES TO GO TO A FULL MOVEMENT INTERSECTION INTO THE COMMUNITY
- **SIGNIFICANT AD VALOREM TAX INCREASE OF APPROXIMATELY \$1,200,000 PER ANNUM AT COMPLETION (THE CURRENT TAX IS APPROXIMATELY \$225,000)**
- **COMMUNITY IMPROVEMENTS:**
 - IMPROVED COMMUNITY CONNECTIVITY: NEW SIDEWALKS AND BIKE LANES, CONGESTION RELIEF FROM FORDHAM AND PEDESTRIAN ACCESS THROUGH OUR PROJECT
 - NEW DEVELOPMENT WILL INCREASE GREEN SPACE AND RECREATION SPACE
 - STORM WATER IMPROVEMENTS THAT WILL BE A SIGNIFICANT ENHANCEMENT FOR THIS AREA
- **MIX OF HOUSING CHOICES**
 - URBAN PARKING DECK BUILDING WITH 1, 2, AND 3 BEDROOM UNITS RANGING FROM 646 TO 1500 SQUARE FEET
 - GARDEN STYLE BUILDINGS WITH 1, 2, AND 3 BEDROOM UNITS RANGING FROM 605 TO 1450 SQUARE FEET
 - FUTURE POTENTIAL SENIOR HOUSING PROJECT ON FINAL PHASE
 - FUTURE POTENTIAL COMMERCIAL IF BYPASS LANE HOMES COULD BE REASONABLY ACQUIRED
- **HOUSING AFFORDABILITY**
 - \$1,500,000 CONTRIBUTION TO THE TOWN OF CHAPEL HILL'S HOUSING AFFORDABILITY INITIATIVES
 - THE PROJECT TEAM IS WORKING WITH THE TOWN TO OPTIMIZE THE REINVESTMENT OF THIS CONTRIBUTION BACK INTO THIS PROJECT
 - IN ADDITION TO THIS CONTRIBUTION, THE PROJECT WILL HAVE UNITS THAT MEET VARIOUS EXISTING AMI LEVELS:
 - 1 BEDROOM (1 PERSON)
 - 80% AMI @ \$1,028/MONTH: targeting 30 units at or below this level
 - 100% AMI @ \$1,284/MONTH: targeting 50 units at or below this level
 - 120% AMI @ \$1,541/MONTH: targeting 30 units at or below this level
 - 2 BEDROOM (2 PEOPLE)
 - 100% AMI @ \$1,467/MONTH: targeting 10 units at or below this level
 - 120% AMI @ \$1,761/MONTH: targeting 30 units at or below this level
 - 3 BEDROOM (4 PEOPLE)
 - 100% AMI @ \$1,833/MONTH: targeting 1-5 units at or below this level

